

About us 关于我们

18⁺
年
从事阀门事业

50⁺
个
产品应用行业

200⁺
种
产品种类多元化

10⁺
种
产品执行标准

温州优立机械有限公司创建于2002年，从事阀门事业近20年。总部位于温州市龙湾区高新技术园区度山工业区。是一家集研发、铸造、生产、销售及服务为一体的全能型阀门制造企业。

企业拥有现代化标准生产车间，雄厚的经济实力，完善的生产设备，专业的技术团队，是富睿稳步发展的基石。富睿产品以品质至上赢得口碑，靠品类丰富占有市场。所生产产品都经过严格的检验与检测，做到有瑕疵产品坚决不进入下一流程，不合格产品坚决不出车间，不会让不良品流入客户手中。为稳步拓展市场，企业现有研发生产的产品种类200多个型号，1000多种规格。

专业制造生产不锈钢阀门系列：电动阀门、气动阀门、L型三通球阀，T型三通球阀，单L型四通球阀、双L四通球阀、T型四通球阀、T型五通球阀、L型五通球阀、非标五通球阀、过滤器，闸阀，止回阀，截止阀，S型截止阀，B型截止阀，旋启式止回阀，立式止回阀，Y型过滤器，对夹式止回阀，快速接头，KJA槽车快速接头，KJB槽车快速接头，不锈钢快速接头，铝合金快速接头，铜制快速接头，液压快速接头，一片式球阀，二片式球阀，三片式球阀，对焊球阀，快装球阀，承插焊球阀，内螺纹球阀，法兰球阀，卫生级球阀，卫生级隔膜阀，卫生级法兰球阀，Z15闸阀，H14止回阀，H12止回阀，JB11截止阀，JS11截止阀，GY11过滤器，H71止回阀，Z41闸阀，H44止回阀，H42止回阀，J41截止阀，GY41过滤器，Q11球阀，Q15球阀，Q14球阀，Q21球阀，Q41球阀，Q61球阀，Q71球阀，Q81球阀，G81隔膜阀，D81蝶阀，管件、弯头、三通、堵头、管帽、活接、外丝、内丝、皮干接、等其它非标产品订做。

公称通径：DN15mm-DN300mm (1/4 " -12 ")。
公称压力：PN0.6Mpa-6.4Mpa (Class150LB-600LB)。
连接方式：丝扣，快装，法兰，焊接等方式。
驱动方式：进口 (国产) 气动，电动，蜗轮，液动等方式。

产品广泛应用于水务，石油，化工，造纸，电站，船舶，轻纺，建筑，水利，制药，环保等诸多行业。在标准化规范化发展前提下，企业先后获得国家压力管道TS证书、国际质量体系ISO9001-2015证书、欧盟CE证书、多枚国家商标证书、多项专利等证书和荣誉。产品也远销海外，遍及美国，日本，欧洲，东南亚，南非等国家和地区。企业以创新带发展、质量求生存、管理促效益、诚信引客户的经营理念，“诚心服务、注重品牌” 取信于新老客户，服务于新老客户。欢迎各界新老朋友来电来函咨询。真诚欢迎各界用户前来参观、考察、洽谈业务！



YouLi Machinery Co., Ltd. was founded in 2002 and has been engaged in valve business for nearly 20 years. The headquarter is located in Dushan Industrial Zone, High-tech Park, Longwan District, Wenzhou City. It is an all-round valve manufacturing enterprise integrating R&D, casting, production, sales and service.

The company has modern standard production workshops, strong economic strength, perfect production equipment, and professional technical team, which are the cornerstones of Fu Rui's steady development. Furui's products have won a reputation for quality first, and they occupy the market with rich categories. The products produced have undergone strict inspection and testing, so that defective products will never enter the next process, unqualified products will never leave the workshop, and defective products will not flow into the hands of customers. In order to steadily expand the market, the company currently develops and produces more than 200 types of products and more than 1,000 specifications.

Professional manufacturing and production of stainless steel valve series: electric valves, pneumatic valves, L-type three-way ball valves, T-type three-way ball valves, single L-type four-way ball valves, double-L four-way ball valves, T-type four-way ball valves, T-type five-way ball valves, L-type five-way ball valve, non-standard five-way ball valve, filter, gate valve, check valve, stop valve, S-type stop valve, B-type stop valve, swing check valve, vertical check valve, Y-type filter, Wafer check valve, quick coupling, KJA tank truck quick coupling, KJB tank truck quick coupling, stainless steel quick coupling, aluminum alloy quick coupling, copper quick coupling, hydraulic quick coupling, one-piece ball valve, two-piece ball valve, Three-piece ball valve, butt welding ball valve, quick-fit ball valve, socket welding ball valve, internal thread ball valve, flange ball min, sanitary ball valve, sanitary diaphragm valve, sanitary flange ball valve. Z15 gate valve, H14 check valve, H12 check valve, JB11 globe valve, JS11 globe valve, GY11 filter, H71 check valve, Z41 gate valve, H44 check valve, H42 check valve, J41 globe valve, GY41 filter, Q11 ball valve, Q15 ball valve, Q14 ball valve, Q21 ball valve, Q41 ball valve, Q61 ball valve, Q71 ball valve, Q81 ball valve, G81 diaphragm valve, D81 butterfly valve, pipe fittings, elbows, three-way, plugs, pipe caps, unions, outer wires, inner wires, skin dry Other non-standard products are customized.

Nominal diameter: DN15mm-DN300mm (1/4"-12").
Nominal pressure: PN0.6Mpa-6.4Mpa (Class150LB-600LB).
Connection methods: threaded, quick installation, flange, welding, etc.
Drive mode: imported (domestic) pneumatic, electric, worm gear, hydraulic, etc.

Products are widely used in water, petroleum, chemical, paper, power station, shipbuilding, textile, construction, water conservancy, pharmaceutical, environmental protection and many other industries. Under the premise of standardized development, the company has successively obtained the national pressure pipeline TS certificate, the international quality system ISO9001-2015 certificate, the EU CE certificate, multiple national trademark certificates, multiple patents and other certificates and honors. Products are also exported to overseas, all over the United States, Japan, Europe, Southeast Asia, South Africa and other countries and regions. With the business philosophy of innovation to drive development, quality to survive, management to promote efficiency, and integrity to attract customers, the company "sincere service and focus on brand" wins the trust of new and old customers and serves new and old customers. Welcome new and old friends from all walks of life to call or write for consultation. Sincerely welcome users from all walks of life to visit, inspect and negotiate business!

目录

Contents

BYA 圆型压力人孔 BYA Round outward manway with pressure	06	BYGCD 侧入式袋式过滤器 BYGCD Side entry bag filter	16
BYB 圆型常压人孔 BYB Round outward manway	07	BYGDD 顶入式袋式过滤器 BYGDD Top entry bag filter	18
BYB-B 圆型常压人孔 (上部密封) BYB-B Round outward manway (upper seal)	08	BYGDS 多袋式过滤器 BYGDS Multi bag filter	20
BYB-C 圆型常压糖化人孔 BYB-C Round manway with sight glass	09	BYGDX 单芯卫生级液体过滤器 BYGDX Single cartridge sanitary filter	22
BYC 内开式椭圆人孔 BYC Oval inward manway	10	BYGLD 多芯液体过滤器 BYGLD Multi Cartridge Sanitary Filter	24
BYC-B 内开式带斜边椭圆人孔 BYC-B Oval inward manway with bevel edge	11	BYGDB 大饼式过滤器 BYGDB Lenticular filter	26
BYD 圆形带视镜压力人孔 BYD Round outward manway with sight glass	12	BYGJM 精密液体过滤器 BYGJM Precision liquid filter	28
BYE 双锁方型人孔 BYE Rectangular manway with two intersectant arms	13	BYGSF 工业级精密过滤器 BYGSF Industrial grade precision liquid filter	32
BYE-B 单锁方型人孔 BYE-B Rectangular manway with one intersectant arms	14	BYGRP 工业过滤器 BYGRP Industrial cartridge filter	36
BYF 全通视镜压力人孔 BYF Full view mirror pressure manhole	15		



订购指南
How to order



型号 Type	规格 Size	材质 Material	内表面处理 Inner surf.	外表面处理 Outer surf.
BYA	400	304	0.8μm-0.4μm	亚光 Matte
数量 Qty	手轮数量 Handwheel-num	高度 Height	密封材质 Gasket	承受压力 Pressure
20	6个塑料手轮 6 Plastic	100mm	硅胶 Silicone	1-3bar



技术参数
Technical parameters

Size	OD mm	t mm	H mm	t1 mm	手轮数量 Handwheel- num	Pres (Bar)
200	206	3	100	3	4	1 - 3
300	306	3	100	3	4	1 - 3
350	356	3	100	3	5	1 - 3
400	406	3	100	3	6	1 - 3
430	436	3	100	3	6	1 - 3
450	456	3	100	3	6	1 - 3
500	508	4	100	3	6	1 - 3
600	608	4	100	4	6	1 - 3

高度 (H) 和颈圈 (t) 及盖子 (t1), 可根据您的需求定制。
Height (H) and Frame (t) and cover (t1), can be changed according to your requirement.



特点
Feature

- 密封材质: 硅胶, 三元乙丙, 丁腈, 氟橡胶符合 FDA177.2600;
 - 材质: 304(1.4301), 316L(1.4404)
 - 内表面处理: 0.8μm-0.4μm
 - 外表面处理: 镜面抛光, 亚光, 喷砂处理。
- Gasket: Silicone/EPDM/NBR/FPM in accordance with FDA 177.2600.
 - Material: 304(1.4301), 316L(1.4404)
 - Internal surface: 0.8μm-0.4μm
 - Outside surface: Mirror polished, Matte, sand-blasting finished.



订购指南
How to order



型号 Type	规格 Size	材质 Material	内表面处理 Inner surf.	外表面处理 Outer surf.
BYB	400	304	0.8μm-0.4μm	亚光 Matte
数量 Qty	手轮数量 Handwheel-num	高度 Height	密封材质 Gasket	承受压力 Pressure
20	1个塑料手轮 1 Plastic	100mm	硅胶 Silicone	0-0.1 bar



技术参数
Technical parameters

Size	OD mm	t mm	H mm	t1 mm	Pres (Bar)
200	200	2.5	100	2	0 - 0.1
219	219	2.5	100	2	0 - 0.1
300	300	2.5	100	2	0 - 0.1
350	350	2.5	100	2	0 - 0.1
400	400	3	100	2.5	0 - 0.1
430	430	3	100	2.5	0 - 0.1
450	450	3	100	2.5	0 - 0.1
500	500	3	100	2.5	0 - 0.1
600	600	4	100	3	0 - 0.1
420X300 (Oval- 椭圆)	420X300	3	100	2.5	0 - 0.1

高度 (H) 和颈圈 (t) 及盖子 (t1) 可根据您的需求定制, 可另加视镜。
Height(H) and Frame (t) and cover (t1) can be changed according to your requirement, also include sight glass.



特点
Feature

- 密封材质: 硅胶, 三元乙丙, 丁腈, 氟橡胶符合 FDA177.2600;
 - 材质: 304(1.4301), 316L(1.4404)
 - 内表面处理: 0.8μm-0.4μm
 - 外表面处理: 镜面抛光, 亚光, 喷砂处理。
- Gasket: Silicone/EPDM/NBR/FPM in accordance with FDA 177.2600.
 - Material: 304(1.4301), 316L(1.4404)
 - Internal surface: 0.8μm-0.4μm
 - Outside surface: Mirror polished, Matte, sand-blasting finished.

BYB-B 圆型常压人孔 (上部密封)
Round Outward Manway (Upper Seal)



BYB-C 圆型常压糖化人孔
Round Manway With Sight Glass

订购指南
How to order

型号 Type	规格 Size	材质 Material	内表面处理 Inner surf.	外表面处理 Outer surf.
BYB-B	400	304	0.8μm-0.4μm	0.8μm-0.4μm
数量 Qty	手轮数量 Handwheel-num	高度 Height	密封材质 Gasket	承受压力 Pressure
20	1个塑料手轮 1 Plastic	100mm	硅胶 Silicone	0-1bar

技术参数
Technical parameters

Size	OD mm	t mm	H mm	t1 mm	Pres (Bar)
300	304	2	100	1.5	0 - 1
350	354	2	100	1.5	0 - 1
430	434	2	100	1.5	0 - 1
450	454	2	100	1.5	0 - 1
500	504	2	100	1.5	0 - 1

高度 (H) 和颈圈 (t) 及盖子 (t1) 可根据您的需求定制。
Height(H) and Frame (t) and cover (t1) can be changed according to your requirement.

特点
Feature

- 密封材质: 硅胶, 三元乙丙, 丁腈, 氟橡胶符合 FDA177.2600;
- 材质: 304(1.4301), 316L(1.4404)
- 内表面处理: 0.8μm-0.4μm
- 外表面处理: 镜面抛光, 亚光, 喷砂处理。

- Gasket: Silicone/EPDM/NBR/FPM in accordance with FDA 177.2600.
- Material: 304(1.4301), 316L(1.4404)
- Internal surface: 0.8μm-0.4μm
- Outside surface: Mirror polished, Matte, sand-blasting finished.

订购指南
How to order

型号 Type	规格 Size	材质 Material	内表面处理 Inner surf.	外表面处理 Outer surf.
BYB-C	400	304	0.8μm-0.4μm	亚光 Matte
数量 Qty	手轮数量 Handwheel-num	高度 Height	密封材质 Gasket	承受压力 Pressure
20	1个塑料手轮 1 Plastic	100mm	硅胶 Silicone	0-0.2bar

技术参数
Technical parameters





Size	OD mm	t mm	H mm	t1 mm	视镜 Sight Glass	Pres (Bar)
350	355	2.5	100	2.5	DN80	0-0.2
400	406	3	100	3	DN100	0-0.2
450	456	3	100	3	DN150	0-0.2
500	506	3	100	3	DN200	0-0.2
600	608	4	100	3	DN400/500	0-0.2

高度 (H) 和颈圈 (t) 及盖子 (t1) 可根据您的需求定制。
Height(H) and Frame (t) and cover (t1) can be changed according to your requirement.

特点
Feature

- 密封材质: 硅胶, 三元乙丙, 丁腈, 氟橡胶符合 FDA177.2600;
- 材质: 304(1.4301), 316L(1.4404)
- 内表面处理: 0.8μm-0.4μm
- 外表面处理: 镜面抛光, 亚光, 喷砂处理。

- Gasket: Silicone/EPDM/NBR/FPM in accordance with FDA 177.2600.
- Material: 304(1.4301), 316L(1.4404)
- Internal surface: 0.8μm-0.4μm
- Outside surface: Mirror polished, Matte, sand-blasting finished.



BYC 内开式椭圆人孔
Oval Inward Manway



BYC-B 内开式带斜边椭圆人孔
Oval Inward Manway With Bevel Edge

订购指南
How to order

型号 Type	规格 Size	材质 Material	内表面处理 Inner surf.	外表面处理 Outer surf.
BYC	430×330	304	0.8μm-0.4μm	亚光 Matte
数量 Qty	手轮数量 Handwheel-num	高度 Height	密封材质 Gasket	承受压力 Pressure
20	1个不锈钢Y型手轮 1 Y stainless steel	75mm	硅胶 Silicone	1-3bar

技术参数
Technical parameters

Size	OD mm L1×L2	t mm	H mm	t1 mm	Pres (Bar)
430×330	430×330	8	75	2.5	1 - 3
435×335	435×335	10	75	2.5	1 - 3
450×350	450×350	8	75	3	1 - 3
530×430	530×430	10	75	3	1 - 3
535×435	535×435	12	75	3	1 - 3
635×525	635×525	12	80	3	1 - 3

高度 (H) 和颈圈 (t) 及盖子 (t1) 可根据您的需求定制。
Height(H) and Frame (t) and cover (t1) can be changed according to your requirement.

特点
Feature

- 密封材质：硅胶，三元乙丙，丁腈，氟橡胶符合 FDA177.2600;
- 材质：304(1.4301), 316L(1.4404)
- 内表面处理：0.8μm-0.4μm
- 外表面处理：镜面抛光，亚光，喷砂处理。

- Gasket: Silicone/EPDM/NBR/FPM in accordance with FDA 177.2600.
- Material: 304(1.4301), 316L(1.4404)
- Internal surface: 0.8μm-0.4μm
- Outside surface: Mirror polished, Matte, sand-blasting finished.

订购指南
How to order

型号 Type	规格 Size	材质 Material	内表面处理 Inner surf.	外表面处理 Outer surf.
BYC-B	580×480	304	0.8μm-0.4μm	亚光 Matte
数量 Qty	手轮数量 Handwheel-num	高度 Height	密封材质 Gasket	承受压力 Pressure
20	1个不锈钢Y型手轮 1 Y stainless steel	133mm	硅胶 Silicone	1-3bar

技术参数
Technical parameters



Size	OD mm L1×L2	t1 mm	H mm	t2 mm	Pres (Bar)
550×450	550×450	3	80	4	1 - 3
550×450A	550×450	4	80	5	1 - 3
565×465	565×465	4	100	5	1 - 3
580×480	580×480	4	133	5	1 - 3

高度 (H) 和颈圈 (t) 及盖子 (t1) 可根据您的需求定制。
Height(H) and Frame (t) and cover (t1) can be changed according to your requirement.

特点
Feature

- 密封材质：硅胶，三元乙丙，丁腈，氟橡胶符合 FDA177.2600;
- 材质：304(1.4301), 316L(1.4404)
- 内表面处理：0.8μm-0.4μm
- 外表面处理：镜面抛光，亚光，喷砂处理。

- Gasket: Silicone/EPDM/NBR/FPM in accordance with FDA 177.2600.
- Material: 304(1.4301), 316L(1.4404)
- Internal surface: 0.8μm-0.4μm
- Outside surface: Mirror polished, Matte, sand-blasting finished.





订购指南
How to order

型号 Type	规格 Size	材质 Material	内表面处理 Inner surf.	外表面处理 Outer surf.
BYD	450	304	0.8μm-0.4μm	亚光 Matte
数量 Qty	手轮数量 Handwheel-num	高度 Height	密封材质 Gasket	承受压力 Pressure
20	6个塑料手轮 6 Plastic	100mm	硅胶 Silicone	1-3bar

技术参数
Technical parameters



Size	OD mm	t mm	H mm	t1 mm	视镜 Sight glass	Pres (Bar)
200	206	3	100	3	DN80	1 - 3
300	306	3	100	3	DN80	1 - 3
350	356	3	100	3	DN80	1 - 3
400	406	3	100	3	DN80	1 - 3
430	436	3	100	3	DN80	1 - 3
450	456	3	100	3	DN80	1 - 3
500	508	4	100	3	DN100	1 - 3
600	608	4	100	4	DN100	1 - 3

高度 (H) 和颈圈 (t) 及盖子 (t1), 视镜可根据您的需求定制。
Height(H) and Frame (t) and cover (t1), sight glass can be changed according to your requirement.

特点
Feature

- 密封材质: 硅胶, 三元乙丙, 丁腈, 氟橡胶符合 FDA177.2600;
- 材质: 304(1.4301), 316L(1.4404)
- 内表面处理: 0.8μm-0.4μm
- 外表面处理: 镜面抛光, 亚光, 喷砂处理。

- Gasket: Silicone/EPDM/NBR/FPM in accordance with FDA 177.2600.
- Material: 304(1.4301), 316L(1.4404)
- Internal surface: 0.8μm-0.4μm
- Outside surface: Mirror polished, Matte, sand-blasting finished.





订购指南
How to order

型号 Type	规格 Size	材质 Material	内表面处理 Inner surf.	外表面处理 Outer surf.
BYE	435×335	304	0.8μm-0.4μm	0.8μm-0.4μm
数量 Qty	手轮数量 Handwheel-num	高度 Height	密封材质 Gasket	承受压力 Pressure
20	2个不锈钢Y型手轮 2 Y stainless steel	80mm	硅胶 Silicone	1-3bar

技术参数
Technical parameters

Size	OD mm L1×L2	t mm	H mm	t1 mm	Pres (Bar)
250×150	250×150	5	80	1.5	1 - 3
235×185	235×185	5	80	1.5	1 - 3
435×335	435×335	8	80	3	1 - 3
535×435	535×435	8	100	3	1 - 3
700×500	700×500	12	100	3	1 - 3

高度 (H) 和颈圈 (t) 及盖子 (t1), 视镜可根据您的需求定制。
Height(H) and Frame (t) and cover (t1), sight glass can be changed according to your requirement.



特点
Feature

- 密封材质: 硅胶, 三元乙丙, 丁腈, 氟橡胶符合 FDA177.2600;
- 材质: 304(1.4301), 316L(1.4404)
- 内表面处理: 0.8μm-0.4μm
- 外表面处理: 镜面抛光, 亚光, 喷砂处理。

- Gasket: Silicone/EPDM/NBR/FPM in accordance with FDA 177.2600.
- Material: 304(1.4301), 316L(1.4404)
- Internal surface: 0.8μm-0.4μm
- Outside surface: Mirror polished, Matte, sand-blasting finished.

BYE-B

单锁方型人孔 Rectangular Manway With One Intersectant Arms



BYF

全通视镜压力人孔 Full View Mirror Pressure Manhole


订购指南 How to order

型号 Type	规格 Size	材质 Material	内表面处理 Inner surf.	外表面处理 Outer surf.
BYE-B	435×335	304	0.8μm-0.4μm	0.8μm-0.4μm
数量 Qty	手轮数量 Handwheel-num	高度 Height	密封材质 Gasket	承受压力 Pressure
20	1个不锈钢Y型手轮 1 Y stainless steel	80mm	硅胶 Silicone	1-3bar

技术参数 Technical parameters

Size	OD mm L1×L2	t mm	H mm	t1 mm	Pres (Bar)
250×150	250×150	5	80	1.5	1 - 3
235×185	235×185	5	70	1.5	1 - 3
435×335	435×335	8	80	3	1 - 3
535×435	535×435	8	100	3	1 - 3
700×500	700×500	12	100	3	1 - 3




高度 (H) 和颈圈 (t) 及盖子 (t1), 视镜可根据您的需求定制。
Height(H) and Frame (t) and cover (t1), sight glass can be changed according to your requirement.



特点 Feature

- 密封材质: 硅胶, 三元乙丙, 丁腈, 氟橡胶符合 FDA177.2600;
- 材质: 304(1.4301), 316L(1.4404)
- 内表面处理: 0.8μm-0.4μm
- 外表面处理: 镜面抛光, 亚光, 喷砂处理。

- Gasket: Silicone/EPDM/NBR/FPM in accordance with FDA 177.2600.
- Material: 304(1.4301), 316L(1.4404)
- Internal surface: 0.8μm-0.4μm
- Outside surface: Mirror polished, Matte, sand-blasting finished.



订购指南 How to order

型号 Type	规格 Size	材质 Material	内表面处理 Inner surf.	外表面处理 Outer surf.
BYE-B	400	304	0.8μm-0.4μm	0.8μm-0.4μm
数量 Qty	手轮数量 Handwheel-num	高度 Height	密封材质 Gasket	承受压力 Pressure
20	6个不锈钢Y型手轮 6Y stainless steel	100mm	硅胶 Silicone	1.5

技术参数 Technical parameters

Size	A mm	C mm	B mm	Pres (Bar)
300	300	3	100	1 - 3
350	350	3	100	1 - 3
400	400	3	100	1.5
450	450	3	100	1.5
500	500	3	100	1
600	600	3	100	0.5

高度 (H) 和颈圈 (t) 及盖子 (t1), 视镜可根据您的需求定制。
Height(H) and Frame (t) and cover (t1), sight glass can be changed according to your requirement.

特点 Feature

- 密封材质: 硅胶, 三元乙丙, 丁腈, 氟橡胶符合 FDA177.2600;
- 材质: 304(1.4301), 316L(1.4404)
- 内表面处理: 0.8μm-0.4μm
- 外表面处理: 镜面抛光, 亚光, 喷砂处理。

- Gasket: Silicone/EPDM/NBR/FPM in accordance with FDA 177.2600.
- Material: 304(1.4301), 316L(1.4404)
- Internal surface: 0.8μm-0.4μm
- Outside surface: Mirror polished, Matte, sand-blasting finished.

BYGCD

侧入式袋式过滤器
Side Entry Bag Filter



经济型单袋式过滤器
Single Bag Filter

- BYGCD 侧入式袋式过滤器，一款配合滤袋使用的袋式过滤器，用于一些粗过滤及预过滤环节。
 - 侧进下出或侧进侧出的结构，有效地节省了过滤器的空间，整个结构经济合理。
 - 用压环、弹簧压紧滤袋环口，保证了过滤器与滤袋之间良好的密封。
 - 可调支脚，安装尺寸可根据现场要求快速调整。
- BYGCD Side-entry bag filter with single filter bag is for some coarse filtration and pre-filtration process.
 - Side entry structure is a economical and reasonable design which can effectively save space of the filter.
 - Pressure ring and the spring ensure good seal between the filter and the filter bag.
 - With adjustable legs, the installation size can be adjusted according to the requirements of the particular spot.

操作条件
Operating conditions

最大操作压力 Max operating pressure	0.6MPa、1.0MPa
最大操作温度 Max operating temperture	150° C


材 料
Material

过滤器壳体 Shell	304、316L
吊环螺栓 Eyebolt	304
可调支脚 Stabilizer blade	304
密封圈、垫片 O-ring	三元乙丙橡胶、聚四氟乙烯、氟橡胶、硅橡胶 EPDM,PTFE,Vtion,Silicone

表面处理
Surface finish

处理类型 Finish type	机械抛光、电解抛光、喷砂 Mechanical / Electrolytical polishing Sand blasting
抛光精度 Polishing precision	内壁 0.6 μm Inner surface Ra ≤ 0.6 μm 外壁 0.8 μm Outside surface Ra ≤ 0.8 μm 支撑滤篮 0.6 μm Basket 0.6 μm

常规结构
Structure



侧入式袋式过滤器
Side entry bag filter

尺寸参数表
Dimension parameters

	模压盖 / 平盖 Molded cover / flat cover		平盖 Cover	
	1 号袋 1#Bag	2 号袋 2#Bag	3 号袋 3#Bag	4 号袋 4#Bag
A: 总高 (不含压力表) Total height	990	1365	525	635
B: 进口中心距 The distance from inlet to center	147		92	
C: 直径 Shell diameter	Φ 204	Φ204	Φ114	Φ114
D1: 进口离地高度 The height from inlet to ground	835	1025	445	555
D2: 出口离地高度 The height from outlet to ground	250		300	
N1、N2: 进出口尺寸 In-outlet size	1.5" 或 2"		1" 或 1.5"	
E: 可调支脚高度 Stabilizer blade	500	800	300	400
最大流量 Max flow m³/h	20	40	6	12

上表数据为标准型，仅供参考，可根据客户要求定制：未注长度单位为 mm。
The above-mentioned data is the standard, it can customize according to customer's requirements.

连 接
Connection

壳体连接 Connection of shell	法兰 Flange
进出口 N1、N2 In-outlet	法兰、快装、螺纹 Flange,Tri-clamp,Thread
压力表 N3 (选配) N3 Pressure gauge(option)	1.5" 快装 Tri-clamp (1 号袋 #Bag / 2 号袋 #Bag) M14×1.5 内螺纹 Female thread (3 号袋 #Bag / 4 号袋 #Bag)
排气阀 N4 (选配) N4 Vent valve(option)	1/4" 外螺纹 Male thread

BYGCD 选型表
Selection table

滤袋数量 Qty. of bag filter	滤袋型号 Model of bag filter	壳体材料 Shell material	进出口连接 In-outlet connection	密封圈 O-ring
1P	2S	4	F	E
1P=1 袋 Pc	1S=1 号袋 1#Bag: Φ180×430	4=304	F= 法兰 Flange	E= 三元乙丙橡胶 EPDM
	2S=2 号袋 1#Bag: Φ180×810	6=316L	K= 快装 Tri-clamp	P= 聚四氟乙烯 PTFE
	3S=3 号袋 1#Bag: Φ105×230		L= 螺纹 Thread	V= 氟橡胶 Viton
	4S=4 号袋 1#Bag: Φ105×380			S= 硅橡胶 Silicone

BYGDD

顶入式袋式过滤器
Top Entry Bag Filter



结构最合理的单袋式过滤器
Single Bag Filter With The
Most Reasonable Structure

- BYGDD 顶入式袋式过滤器，一款配合滤袋使用的袋式过滤器，用于一些粗过滤及预过滤环节。
 - 侧面入口进入，再从顶部进入滤袋内的设计，能自动分压，不会产生紊流，减少压力损失，有效保护滤袋。
 - 顶盖全面压紧密封，密封效果更好，杜绝侧漏。
 - 可调支脚，安装尺寸可根据现场要求快速调整。
-
- BYGDD Top Entry Bag Filter Housing for some coarse filtration and pre-filtration process.
 - The design of side entry first and then top entry into the filter bag does not cause turbulence and not reduce pressure because of the stabled pressure. Also this structure effectively protects the filter bag.
 - The top cover is fully pressed and sealed, and the sealing effect is better.
 - With adjustable legs,the installation size can be adjusted according to the requirements of the particular spot.

操作条件
Operating conditions

最大操作压力 Max operating pressure	0.6MPa、1.0MPa
最大操作温度 Max operating temperture	150° C


材 料
Material

过滤器壳体 Shell	304、316L
吊环螺栓 Eyebolt	304
可调支脚 Stabilizer blade	304
密封圈、垫片 O-ring	三元乙丙橡胶、聚四氟乙烯、氟橡胶、硅橡胶 EPDM,PTFE,Vtion,Silicone

表面处理
Surface finish

处理类型 Finish type	机械抛光、电解抛光、喷砂 Mechanical / Electrolytical polishing Sand blasting
抛光精度 Polishing precision	内壁 0.6 μm Inner surface Ra ≤ 0.6 μm 外壁 0.8 μm Outside surface Ra ≤ 0.8 μm 支撑滤篮 0.6 μm Basket 0.6 μm

常规结构
Structure



顶入式袋式过滤器
Top entry bag filter

尺寸参数表
Dimension parameters

	平盖 Cover	
	1 号袋 1#Bag	2 号袋 2#Bag
A: 总高 (不含压力表) Total height	790	1110
B: 进口中心距 The distance from inlet to center	275	
C: 直径 Shell diameter	Φ204	Φ204
D1: 进口离地高度 The height from inlet to ground	620	940
D2: 出口离地高度 The height from outlet to ground	200	
N1、N2: 进出口尺寸 In-outlet size	1.5" 或 2"	
E: 可调支脚高度 Stabilizer blade	550	700
最大流量 Max flow m³/h	20	40

上表数据为标准型，仅供参考，可根据客户要求定制：未注长度单位为 mm。
The above-mentioned data is the standard, it can customize according to customer's requirements.

连 接
Connection

壳体连接 Connection of shell	法兰 Flange
进出口 N1、N2 In-outlet	法兰、快装、螺纹 Flange,Tri-clamp,Thread
压力表 N3 (选配) N3 Pressure gauge(option)	M14×1.5 内螺纹 M14×1.5 Female thread (3#Bag / 4#Bag)
排气阀 N4 (选配) N4 Vent valve(option)	1/4" 外螺纹 Male thread

BYGDD 选型表
Selection table

滤袋数量 Qty. of bag filter	滤袋型号 Model of bag filter	壳体材料 Shell material	进出口连接 In-outlet connection	密封圈 O-ring
1P	2S	4	F	E
1P=1 袋 Pc	1S=1 号袋 1#bag: Φ180×430	4=304	F= 法兰 Flange	E= 三元乙丙橡胶 EPDM
	2S=2 号袋 1#bag: Φ180×810	6=316L	K= 快装 Tri-clamp	P= 聚四氟乙烯 PTFE
	3S=3 号袋 1#bag: Φ105×230		L= 螺纹 Thread	V= 氟橡胶 Viton
	4S=4 号袋 1#bag: Φ105×380			S= 硅橡胶 Silicone

BYGDS

多袋式过滤器
Multi Bag Filter



大流量袋式过滤器
High Flow Bag Filter

- BYGDS 多袋式过滤器，一款配合滤袋使用的袋式过滤器，用于粗过滤及预过滤环节。
- BYGDS 多袋式过滤器标配 01 号滤袋或 02 号滤袋，标准模式为 2 袋 ~12 袋，定制最大生产到 24 袋，基本能满足各类流量的要求。
- BYGDS Multi bags filter, for some coarse filtration and pre-filtration process.
- BYGDS Standard No.01 bag or 02 bag, the standard model for 2 ~ 12 bags, and the maximum production customized to 24 bags can basically meet the requirements of various types of flow.


产品特点
Feature

- 处理流量大，适用寿命长。
- 滤器设计紧凑，减少占地空间，同事减少液体的损失。
- 侧进底出的设计确保液体介质可被完全排放，同时采用了正切位出口供选择，使得排污彻底，工人操作方便。
- 内部独特的三点压紧装置确保良好的滤袋密封性，避免液体旁漏。
- 多袋过滤器壳体可采用转臂 + 吊环螺栓设计或快开设计，操作方便，经济实用。
- Large flow, Long service life.
- Compact design can reduce occupied space and the loss of liquid.
- Side entry and bottom out ensure that liquid medium can be completely discharged, the tangential position outlet, discharging pollution thoroughly, is convenient to be operating.
- The unique three- point clamp device ensures good sealing and avoid liquid side leakage.
- The filter housing can add swing arm and the eyebolt or quick-open design, operating conveniently and economically.

典型的应用
Application

- 食品及饮料；生物工程及医药；石化及化工；汽车制造；石油及天然气；电子及电镀；涂料、油漆、油墨；核电与火电及废液过滤；摄影胶片生产工艺液体过滤；日用化工的液体和气体净化；机械加工及制冷行业各种冷却液过滤；纺织、印染、造纸行业的各种液体净化。
- Food and beverage; bio engineering and pharmaceutical; petrochemical and chemical; automobile manufacturing; petroleum and natural gas; electronic and natural gas; coating, paint, printing ink; nuclear power and thermal power and waste water filtration; liquid and gas purification of liquid and gas.

常规结构 Structure



材 料 Material

过滤器壳体 Shell	304、316L
吊环螺栓 Eyebolt	304
支脚、摇臂等 Stabilizer blade	304
密封圈、垫片 O-ring	三元乙丙橡胶、聚四氟乙烯、氟橡胶、硅橡胶 EPDM,PTFE,Vtion,Silicone

表面处理 Surface finish

处理类型 Finish type	机械抛光、电解抛光、喷砂 Mechanical / Electrolytical polishing / Sand blasting
抛光精度 Polishing precision	内壁 0.6 μm Inner surface Ra ≤ 0.6 μm 外壁 0.8 μm Outside surface Ra ≤ 0.8 μm 支撑滤篮 0.6 μm Basket 0.6 μm

尺寸参数表 Dimension parameters

	2 袋 2 号袋 2P2S		4 袋 2 号袋 4P4S		6 袋 2 号袋 6P2S	
	花板上侧进底出	花板下侧进侧出	花板上侧进底出	花板下侧进侧出	花板上侧进底出	花板下侧进侧出
A: 总高 (不含压力表) Total height	1880	1530	2030	1600	2130	1700
B: 进口中心距 The distance from inlet to center	300		360	400	440	450
C: 直径 Shell diameter	Φ400		Φ500	Φ550	Φ650	
D1: 进口 N1 离地高度 The height from inlet to ground	1330	950	1425	975	1480	1000
D2: 出口 N2 离地高度 The height from outlet to ground	300		400	350	400	
N1、N2: 进出口尺寸 In-outlet N1、N2 size	4"		4"		5"	

上表数据为标准型，仅供参考，可根据客户要求定制：未注长度单位为 mm。
The above-mentioned data is the standard, it can customize according to customer's requirements.

BYGDS 选型表 Selection table

滤袋数量 Qty. of bag filter	滤袋型号 Model of bag filter	壳体材料 Shell material	进出口连接 In-outlet connection	密封圈 O-ring	
3P	2S	4	F	E	
2P=2 袋 Pcs	7P=7 袋 Pcs	1S=1 号袋 #Bag: Φ180×430	4=304	F= 法兰 Flange	E= 三元乙丙橡胶 EPDM
3P=3 袋 Pcs	9P=9 袋 Pcs	2S=2 号袋 #Bag: Φ180×810	6=316L	K= 快装 Tri-clamp	P= 聚四氟乙烯 PTFE
4P=4 袋 Pcs	12P=12 袋 Pcs			L= 螺纹 Thread	V= 氟橡胶 Viton
6P=6 袋 Pcs					S= 硅橡胶 Silicone

BYGDX

单芯卫生级液体过滤器
Single Cartridge Sanitary Filter



无任何清洗死角过滤器
No Dead Corner Filter

- BYGDX 单芯卫生级液体过滤器是一款小流量的高端卫生级过滤器。
- BYGDX 单芯卫生级液体过滤器具有良好的表面和最大的耐腐蚀能力，以达到防治细菌污染的质量标准，卫生级过滤器套筒独特的结构，使每一个套筒的内外表面均没有死角、符合“GMP”规范要求，可完全拆洗，操作方便。

- BYGDX Single Fluid Sanitary Filter is high quality sanitary grade filter which service for small flow rate.
- BYGDX Single Fluid Sanitary Filter have excellent surface treatment and the maximal corrosion-resistant in order to prevent the bacterial contamination. The unique structure of the sanitary filter housing ensures inside and outside surface have no dead corner and conforms to the requirements of GMP, The filter housing can be completely disassembled and washed, easy to operate.

产品特点
Feature

- 超高的抛光等级，内壁采用达到 0.3μm，外壁达到 0.4μm，绝对卫生级抛光。
- 采用强力快装，最高压力可达 0.6MPa、1.0MP。
- 排气阀和排液阀：螺纹套和宝塔接头脱离，在放气和排液时，接软管不会再随着转动。
- 过滤器的支脚采用加强螺纹，不易滑牙，更为耐用；在支脚底部可安装调节螺母，可进行过滤器的高度调节，方便使用。


典型的应用

- 医药行业：各种抗菌素等药液的前置过滤。
- 食品饮料行业：酒类、矿泉水、饮用水的过滤。
- 石油行业：油田注水过滤。
- 电子行业：高纯水前置过滤。
- 化学行业：各种有机溶剂、酸、碱液的过滤。

Appication

- Low the pharmaceutical industry: all kinds of antibiotics such as liquid prefiltering.
- Low food and beverage, wine, mineral water, drinking water filtration.
- Low oil industry, oil field water injection filter.
- Low electronic industry: high pure water prefiltering.
- Low chemical industry: all kinds of organic solvents, acid, alkali liquor filtration.

常规结构 Structure



单芯卫生级液体过滤器 (222 型、226 型)
Single fluid sanitary filter housing
(222tpe、226type)

操作条件 Operating conditions

最大操作压力 Max operating pressure	0.6MPa、1.0MPa
最大操作温度 Max operating temperture	150° C
灭菌 Disinfect	在线或蒸汽灭菌：121° C/30min Online or steam sterilization: 121° C/30min

材 料 Material

过滤器壳体 Shell	304、316L
排气 / 液阀 Vent / Drain valve	304
快装、支脚 Quick-open, stabilizer blade	304
密封圈、垫片 O-ring	三元乙丙橡胶、聚四氟乙烯、氟橡胶、硅橡胶 EPDM, PTFE,Viton,Silicone

连 接 Connection

壳体连接 Connection of shell	快装 Tri-clamp
进出口 N1,N2 In-outlet	快装 Tri-clamp
压力表 N3 (选配) N3 Pressure gauge(option)	1.5" 卡装 Tri-clamp
排气阀 N4 (选配) N4 Vent valve(option)	M6 Thread
排液阀 N5 (选配) N5 Drain valve (option)	M6 Thread
滤芯接头形式 Cartridges connection	222type, 226type

表面处理 Surface finish

处理类型 Finish type	机械抛光、电解抛光、喷砂 Mechanical / Electrolytical polishing / Sand blasting
抛光精度 Polishing precision	内壁 0.3 μm Inner surface Ra ≤ 0.3 μm 外壁 0.4 μm Outside surface Ra ≤ 0.4 μm

尺寸参数表 Dimension parameters

	1 芯 Pc		
	10"	10"	10"
A: 总高 (不含压力表) Total height	625	625	625
B: 进口中心距 The distance from inlet to center	110		
C: 直径 Shell diameter	Φ101.6		
D: 进口 N1、N2 离地高度 N1, N2 The height from in-outlet to ground	170		
进出口尺寸 In-outlet N1、N2 size	1"		

上表数据为标准型，仅供参考，可根据客户要求定制：未注长度单位为 mm。
The above-mentioned data is the standard, it can customize according to customer's requirements.

BYGDX 选型 Selection table

滤袋数量 Qty. of bag filter	滤袋型号 Model of bag filter	滤芯接头 Cartridges connection	壳体材料 Shell material	进出口连接 In-outlet connection	密封圈 O-ring
1R	20	S	4	K	E
1R=1 芯 Pc	10=10" 滤芯 Cartridge	S=226 型 type	4=304	K= 快装 Tri-clamp	E= 三元乙丙橡胶 EPDM
	20=20" 滤芯 Cartridge	T=222 型 type	6=316L		P= 聚四氟乙烯 PTFE
	30=30" 滤芯 Cartridge				V= 氟橡胶 Viton
	40=40" 滤芯 Cartridge				S= 硅橡胶 Silicone

BYGLD

多芯液体过滤器
Multi Cartridge Sanitary Filter



- 中小流量的卫生级过滤器
Medium & Small Flow Rate Sanitary Filter

 - BYGLD 多芯液体过滤器，可满足中小流量要求。
 - 整体结构（222 型、226 型）按照卫生级要求设计制造；结构物卫生死角，符合“GMP”规范要求，易清洗；排液彻底，无残液顾虑。
 - 对于部分清洗非常苛刻的应用，可将过滤器的花盘做成拆卸式，实现全角度清洗。
 - BYGLD Multi Fluid Sanitary Filter can meet requirement of medium & small flow rate.
 - The structure design and manufacture in accordance with the sanitary grade. It's no dead corner, meet "GMP" standard , easy to clean, drain thoroughly, no residual liquid.
 - For the application of some very harsh cleaning, the filter faceplate made of detachable, full angle cleaning.


- 产品特色
Feature

 - 超高的抛光等级，内壁采用达到 0.3μm，外壁达到 0.4μm，绝对卫生级抛光。
 - 排气阀可选快装形式，可完全拆卸，无卫生死角。
 - 小规格过滤器在支脚底部安装调节螺母，可进行过滤器的高度调节，方便使用。

- The ultra high level of polishing, the inner surface polished to 0.3μm Ra. the outer surface to reach 0.4μm, the absolute hygienic level polishing.
- The vent valve can choose quick-open,can completely disassembled and no dead corner of cleaning.
- Small specification filter installation adjusting nut at the bottom of the Stabilizer blade, can adjust the height of the filter, easy to use.

- 典型的应用
- 医药行业：各种抗菌素等药液的过滤。
 - 食品饮料行业：酒类、矿泉水、饮用水的过滤。
 - 石油行业：油田注水过滤。
 - 电子行业：高纯水过滤。
 - 化学行业：各种有机溶剂、酸、碱液的过滤。

- Application
- Pharmaceutical industry: all kinds of antibiotics and other liquid filtration.
 - Food and beverage industry: wine ,mineral water, drinking water filtration.
 - Oil industry: oil field water injection filtration.
 - Electronics industry: high purity water filtration.
 - Chemical industry: all kinds of organic solvent, acid, lye filtration.



操作条件 Operating conditions

最大操作压力 Max operating pressure	0.6MPa、1.0MPa
最大操作温度 Max operating temperture	150° C
灭菌（卫生级） Disinfect(sanitation)	在线或蒸汽灭菌：121° C/30min Online or steam sterilization: 121° C/30min

材 料 Material

过滤器壳体 Shell	304、316L
排气 / 液阀 Vent / Drain valve	304、316L
吊环螺栓 Eyebolt	304
密封圈、垫片 O-ring	三元乙丙橡胶、聚四氟乙烯、氟橡胶、硅橡胶 EPDM, PTFE,Viton,Silicone

连 接 Connection

壳体连接 Connection of shell	法兰（吊环螺栓）、卡接 Tri-clamp, Flange
进出口 N1,N2 In-outlet	快装 Tri-clamp
压力表 N3（选配） N3 Pressure gauge(option)	1.5" 快装 Tri-clamp
排气阀 N4（选配） N4 Vent valve(option)	1/2" 快装 /M6 螺纹 1/2" Tri-clamp/M6 Thread
排液阀 N5（选配） N5 Drain valve (option)	1/2" 快装 Tri-clamp
滤芯接头形式 Cartridges connection	222 型、226 型（卫生级）DOE（工业级） 222type, 226type(sanitation) DOE type(industrial-grade)

表面处理 Surface finish

处理类型 Finish type	机械抛光、电解抛光、喷砂 Mechanical/Electrolytical polishing/Sand blasting
抛光精度 Polishing precision	内壁 0.3 μm Inner surface Ra ≤ 0.3 μm 外壁 0.4 μm Outside surface Ra ≤ 0.4 μm

尺寸参数表 Dimension parameters

	3 芯（4 芯）3R(4R)				5 芯（6 芯）5R(6R)				7 芯（8 芯）7R(8R)			
	10"	20"	30"	40"	10"	20"	30"	40"	10"	20"	30"	40"
A: 总高（不含压力表） Total height	760	1010	1260	1510	780	1030	1280	1530	805	1055	1305	1555
B: 进口中心距 The distance from inlet to center	160				160				200			
C: 直径 Shell diameter	Φ204				Φ235				Φ273			
D: 进口 N1、N2 离地高度 The height from in-outlet N1, N2 to the ground	200				200				200			
进出口尺寸 In-outlet N1、N2 size	1.5"				2"				2.5"			

上表数据为标准型多芯卫生级液体过滤器，仅供参考，可根据客户要求定制：未注长度单位为 mm。
The above-mentioned data is the standard, it can customize according to customer's requirements.

BYGDX 选型 Selection table

滤袋数量 Qty. of bag filter	滤袋型号 Model of bag filter	滤芯接头 Cartridges connection	壳体材料 Shell material	进出口连接 In-outlet connection	密封圈 O-ring
5R	20	S	4	K	E
3R=3 芯 Pcs	10=10" 滤芯 Cartridge	S=226 型（卫生级）(sanitary grade)	4=304	K= 快装 Tri-clamp	E= 三元乙丙橡胶 EPDM
5R=5 芯 Pcs	20=20" 滤芯 Cartridge	T=222 型（卫生级）(sanitary grade)	6=316L		P= 聚四氟乙烯 PTFE
7R=7 芯 Pcs	30=30" 滤芯 Cartridge	D=DOE 型（卫生级）(industrial-grade)			V= 氟橡胶 Viton
9R=9 芯 Pcs	40=40" 滤芯 Cartridge				S= 硅橡胶 Silicone
12R=12 芯 Pcs					

BYGDB

大饼式过滤器
Lenticular Filter



深层过滤器
Depth Filter

- BYGDB 大饼式过滤器是一种新型深层过滤器，可用于代替硅藻土过滤器，对各类液体中微小杂质进行过滤、澄清、提纯处理。
- 整体结构按照卫生级要求设计制造，料液无残留，极易清洗，高精度抛光；采用下进下出式结构设计，有效避免料液的紊流，提高过滤性能。
- BYGDB 大饼式过滤器最多标配4个滤饼，能满足大流量的过滤要求。

- BYGDB Lenticular Filter is a new type of stacks filter, can be used in place of diatomite filter, for tiny impurities in varied kinds of liquid filtration, clarification, purification.
- The structure is designed and manufactured according to the health level, internal is no dead corner and mirror polishing, it ensure no residual liquid and easy to clean.
- BYGDB Lenticular Filter Housing can maximal install 4 filter stacks, it can fit for big flow requirements .

典型的应用
Application

- 酒类，糖浆，啤酒的微生物和固体过滤。
- 果汁和果汁浓缩灌装前的终端过滤。
- 果汁膜过滤之前的预过滤。
- 酒类，酶溶解，液体胶质，橄榄油的澄清过滤。
- 医药，化工，电子过滤。

- Microbe and solid filtration of alcohol, syrup, beer.
- End filtration of fruit juice and juice concentrate.
- Pre filtering of juice membrane filtration.
- Clarification of alcohol, enzyme dissolution, liquid gum, olive oil.
- Pharmaceutical, chemical, electronic filtration.


产品特点

- 下进下出的结构设计，方便清洗，在进出口可配置专门的排液阀，方便排液。
- 多饼过滤器时，可选择筒体多段开口的形式，方便更换滤饼，减少滤液渗出。

Feature

- Easy to clean, the inlet/outlet can be configured special discharge valve, easy to drain.
- Easy to replace the filter stacks, reduce the filter medium leakage.

常规结构 Structure



操作条件 Operating conditions

最大操作压力 Max operating pressure	0.6MPa
最大操作温度 Max operating temperture	150° C
灭菌 Disinfect	在线或蒸汽灭菌：121° C/30min Online or steam sterilization: 121° C/30min

材 料 Material

过滤器壳体 Shell	304、316L
排气 / 液阀 Vent / Drain valve	304、316L
吊环螺栓 Eyebolt	304
支脚 Stabilizer blade	304
密封圈、垫片 O-ring	三元乙丙橡胶、聚四氟乙烯、氟橡胶、硅橡胶 EPDM, PTFE,Viton,Silicone

连 接 Connection

壳体连接 Connection of shell	法兰 Flange
进出口 N1,N2 In-outlet	法兰 / 快装 / 螺纹 Flange, Tri-clamp, Thread
压力表 N3 (选配) N3 Pressure gauge(option)	1.5" 快装 Tri-clamp
排液阀 N4 (选配) N4 Drain valve(option)	1" 快装 Tri-clamp
排气阀 N5 (选配) N5 Vent valve (option)	1/2" 快装 Tri-clamp

表面处理 Surface finish

处理类型 Finish type	机械抛光、电解抛光 Mechanical / Electrolytical polishing
抛光精度 Polishing precision	内壁 0.3 μm Inner surface Ra ≤ 0.3 μm V 外壁 0.4 μm Outside surface Ra ≤ 0.4 μm

尺寸参数表 Dimension parameters

	12" 滤饼 Filter stacks				16" 滤饼 Filter stacks			
	1 滤饼 (B)	2 滤饼 (B)	3 滤饼 (B)	4 滤饼 (B)	1 滤饼 (B)	2 滤饼 (B)	3 滤饼 (B)	4 滤饼 (B)
A: 总高 (不含压力表) Total height	950	1210	1490	1760	960	1230	1500	1770
B: 进口中心距 The distance from inlet to center	200				250			
C: 直径 Shell diameter	Φ325				Φ450			
D: 进口 N1、N2 离地高度 N1, N2 The height from in-outlet to ground	280				280			
进出口 N1、N2 尺寸 In-outlet N1,N2 size	2"				2"			

上表数据为标准型大饼式过滤器，仅供参考，可根据客户要求定制：未注长度单位为 mm。
The above-mentioned data is the standard, it can customize according to customer's requirements.

BYGDB 选型表 Selection table

滤饼数量 Qty. of bag filter stacks	滤饼型号 Model of bag filter stacks	壳体材料 Shell material	进出口连接 In-outlet connection	密封圈 O-ring
1B	12	4	F	E
1B=1 饼 Pcs	12=12" 滤饼 Filter stacks	4=304	F= 法兰 Flange	E= 三元乙丙橡胶 EPDM
2B=2 饼 Pcs	16=16" 滤饼 Filter stacks	6=316L	K= 快装 Tri-clamp	P= 聚四氟乙烯 PTFE
3B=3 饼 Pcs			L= 螺纹 Screw thread	V= 氟橡胶 Viton
4B=4Pcs				S= 硅橡胶 Silicone



典型的应用

- 医药行业：各种抗菌素等药液的过滤。
- 食品饮料行业：酒类、矿泉水、饮用水的过滤。
- 石油行业：油田注水过滤。
- 电子行业：高纯水过滤。
- 化学行业：各种有机溶剂、酸、碱液的过滤。

Application

- Pharmaceutical industry: all kinds of antibiotics and other liquid filtration.
- Food and beverage industry: wine, mineral water, drinking water filtration.
- Oil industry: oil field water injection filtration.
- Electronics industry: high purity water filtration.
- Chemical industry: all kinds of organic solvent, acid, lye filtration.

大流量的卫生级过滤器

High Flow Sanitary Filter

- BYGJM 精密液体过滤器是大流量多芯卫生级液体过滤器，可满足不同大小的流量要求。
- 整体结构按照卫生级要求设计制造；结构无卫生死角、符合“GMP”规范要求，易清洗；排液彻底，无残液顾虑。
- 对于部分清洗非常苛刻的应用，可将过滤器的花盘做成拆卸式，实现全角度清洗。
- BYGJM Precision liquid filter is a large flow and multi cartridges sanitary liquid filter, can meet the requirements of different sizes of flow rate.
- The structure design and manufacture is in accordance with the sanitary grade. There is no dead corner, meeting "GMP" standard. This product is easy to clean, draining thoroughly, no residual liquid.
- For strict cleaning application, the filter face plate can be designed to be disassembled to achieve full angle cleaning.


产品特点

Feature


- 超高的抛光等级，内壁采用达到 $0.3\mu\text{m}$ ，外壁达到 $0.4\mu\text{m}$ ，绝对卫生级抛光。
- 处理流量大，紧凑设计节约空间。
- 侧进底出的设计确保液体介质可被完全排放，同时采用了正切位出口供选择，使得排污彻底，工人操作方便。
- 15 芯以上过滤器壳体可采用转臂 + 吊环螺栓设计或快开设计，操作方便，经济实用。

- The ultra high level of polishing, the inner surface polished to $0.3\mu\text{m}$ Ra. the outer surface to reach $0.4\mu\text{m}$, the absolute hygienic level polishing.
- Dealing with large flow, compact design saves space.
- The design of side in bottom out ensures that the particles can be completely removed. At the same time, tangent outlet makes sewage discharged thoroughly, and workers operate easily.
- For more than 15 cartridges filter housing, the swing arm and eyebolt or quick open are optional design to operate easily. Also it is a economical and practical design.

常规结构 Structure




带转臂精密液体过滤器（滤芯数量 ≥ 15 芯）
滤芯型号为 40" 滤芯（右图示）
With rotary precision liquid filter(cartridge quantity ≥ 15 pcs) Cartridge model 40" (right picture)



精密液体过滤器（滤芯数量 ≤ 12 芯）
滤芯型号为 30" 滤芯（左图示）
Precision Liquid Filter (cartridge quantity ≤ 12 pcs)
Cartridge model 30" (left picture)

BYGJM

精密液体过滤器
Precision Liquid Filter



操作条件
Operating conditions

最大操作压力 Max operating pressure	0.6MPa、1.0MPa
最大操作温度 Max operating temperture	150° C
灭菌 Disinfect	在线或蒸汽灭菌：121° C/30min Online or steam sterilization: 121° C/30min

材 料
Material

过滤器壳体 Shell	304、316L
排气 / 液阀 Vent / Drain valve	304、316L
吊环螺栓 Eyebolt	304
支脚 Stabilizer blade	304
密封圈、垫片 O-ring	三元乙丙橡胶、聚四氟乙烯、氟橡胶、硅橡胶 EPDM,PTFE,Vtion,Silicone

表面处理
Surface finish

处理类型 Finish type	机械抛光、电解抛光、喷砂 Mechanical / Electrolytical polishing Sand blasting
抛光精度 Polishing precision	内壁 0.3 μm Inner surface Ra ≤ 0.3 μm 外壁 0.4 μm Outside surface Ra ≤ 0.4 μm

连 接
Connection

壳体连接 Connection of shell	法兰 (吊环螺栓) Flange(Eyebolt)
进出口 N1、N2 In-outlet	快装 Tri-clamp
压力表 N3 (选配) N3 Pressure gauge(option)	1.5" 快装 Tri-clamp
排气阀 N4 (选配) N4 Vent valve(option)	1/2" 快装 (12 芯以下) 1/2" Tri-clamp(less than 12pcs) 1.5" 快装 (15 芯以上) 1.5" Tri-clamp (more than 15pcs)
排液阀 N5 (选配) N5 Drain valve (option)	1/2"快装(3芯)1/2" Tri-clamp (3R) 3/4" 快装 (5 芯到 12 芯) 3/4" Tri-clamp (5pcs to 12pcs) 1" 快装 (15 芯以上) 1" Tri-clamp(more than 15pcs)
滤芯接头形式 Cartridges connection	222 型、226 型 222 type, 226 type

尺寸参数表
Dimension parameters

	3 芯 (4 芯) 3R(4R)			5 芯 (6 芯) 5R(6R)		
	20"	30"	40"	20"	30"	40"
A: 总高 (不含压力表) Total height	1123	1373	1623	1145	1395	1645
B: 进口中心距 The distance from inlet to center	142			165		
C: 直径 Shell diameter	Φ204			Φ250		
D1: 进口 N1 离地高度 The height from inlet to ground	540			660		
D2: 出口 N2 离地高度 The height from outlet to ground	300			300		
N1、N2: 进出口尺寸 In-outlet N1、N2 size	1.5"/2"			1.5"/2"/2.5"		
尺寸参数表 Dimension parameters	7 芯 (7R)			8 芯 (8R)		
	20"	30"	40"	20"	30"	40"
	1145	1395	1645	1170	1420	1670
	176.5			190		
	Φ273			Φ300		
	660			660		
	300			300		
	1.5"/2"/2.5"			1.5"/2"/2.5"/3"		
	9 芯 (10 芯) 9R(10R)			12 芯 (11 芯) 12R(11R)		
	20"	30"	40"	20"	30"	40"
	1170	1420	1670	1170	1420	1670
	202.5			215		
	Φ325			Φ350		
	660			660		
	300			300		
	1.5"/2"/2.5"/3"			1.5"/2"/2.5"/3"		
	15 芯 (18 芯) 15R(18R)	21 芯 (21R)	24 芯 (27/30 芯) 24R(27/30R)	36 芯 (36R)	42 芯 (42R)	48 芯 (54 芯) 48R(54R)
	40"	40"	40"	40"	40"	40"
	1947	1959	2026	2036	2044	2067
	240	265	290	315	340	365
	Φ400	Φ450	Φ500	Φ550	Φ600	Φ650
	682	694	714	729	734	744
	300			300		
	3"/3.5"/4"			3"/3.5"/4"		

上表数据为标准型，仅供参考，可根据客户要求定制：未注长度单位为 mm。
The above-mentioned data is the standard, it can customize according to customer's requirements.



大流量的工业级过滤器 High Flow Industrial-Grade Filter

- BYGSF 工业级精密过滤器是专门为工业过滤领域所设计的精密过滤器，可广泛应用于各类化工料液中，满足不同大小的流量要求。
- 采用侧进下出的流体方式，确保在更换滤芯过程中，料液不会溢出，造成污染；过滤器可做三段式结构，筒体上下开口，花盘可拆卸，实现过滤器全可拆卸，特别适用于个别对清洗要求严格的操作环节。
- BYGSF 工业级精密过滤器采用多道抛光处理，保证料液接触面 Ra 达到 $0.6\mu\text{m}$ 接近卫生级要求，全镜面抛光，完全可以应用在高精度料液过滤。
- BYGSF Industrial Grade Precision Liquid Filter is precision filter which is specially designed for industrial field, It can be applied for various chemical materials and meet the requirements of different flow.
- The filter housing using side entry & bottom out flow method, it ensure that the material liquid does not overflow when repalce cartridge in process. The filter housing can be design to three-stage structure, shell can be opened from top and bottom, the filter can be absolutely disassemble. For the application of some very harsh cleaning, the filter can full angle cleaning.
- BYGSF Industrial Grade Precision Liquid Filter use many times polishing process, ensure that the material liquid contact surface Ra reached $0.6\mu\text{m}$ close to the sanitary requirement, the filter polished is mirror polished. It can be applied in high precision liquid filtration.


产品特点

- 筒体可做成上下开口形式，即方便更换滤芯，又能实现侧底清洗。
- 过滤器花盘可做成拆卸式，实现侧底清洗。
- 配有双排液口形式，分别在筒体的花盘上部和过滤器的底部，排液方便、侧底。
- 侧进底出的设计确保液体介质可被完全排放，同时采用了正切位出口供选择，使得排污彻底，工人操作方便。
- 15 芯以上过滤器壳体采用转臂 + 吊环螺栓设计或快开设计，操作方便，经济实用。

Feature

- Filter can be made into the form of top and bottom openings, which is convenient to replace the filter and to clean thoroughly.
- The filter faceplate can be made into a detachable type, to achieve thorough cleaning.
- Two drain vents, respectively in the top of the disk and the bottom of the filter, let discharging easy and complete.
- Side in and bottom out, this design ensures that the liquid can be completely discharged. At the same time, tangent outlet makes sewage discharged thoroughly, and workers operate easily.
- For more than 15 cartridges filter housing, the swing arm and eyebolt or quick open are optional design to aperate easily. Also it is a economical and practical design.

常规结构 Structure




222 型、226 型

工业级精密过滤器（滤芯数量 ≥ 15 芯）
滤芯型号为 40" 滤芯（右图示）
Industrial Grade Precision Liquid Filter(cartridge quantity ≥ 15 pcs)
Cartridge model 40"(right picture)

典型的应用

- 水处理：各种水质的过滤。
- 食品饮料行业：酒类、矿泉水、饮用水的过滤。
- 化学行业：各种有机溶剂、酸、碱液的过滤。



DOE 型

222 型、226 型


工业级精密过滤器（滤芯数量 ≤ 12 芯）
滤芯型号为 30" 滤芯（左 / 中图示）
Industrial Grade Precision Liquid Filter (cartridge quantity ≤ 12 pcs)
Cartridge modle 30"(left picture)

Application

- Water Finish: all kinds of water filtration.
- Food & beverage: wine ,mineral water, drinking water filtration.
- Chemical industry: all kinds of organic solvents, acid, alkali, filtration.



工业级精密过滤器
Industrial Grade Precision Liquid Filter



操作条件
Operating conditions

最大操作压力 Max operating pressure	0.6MPa、1.0MPa
最大操作温度 Max operating temperture	150° C

表面处理
Surface finish

处理类型 Finish type	机械抛光、电解抛光 Mechanical / Electrolytical polishing
抛光精度 Polishing precision	内壁 0.6 μm Inner surface Ra ≤ 0.6 μm 外壁 0.8μm Outside surface Ra ≤ 0.8μm

材料
Material

过滤器壳体 Shell	304、316L
排气 / 液阀 Vent / Drain valve	304、316L
吊环螺栓 Eyebolt	304
支脚 Stabilizer blade	304
密封圈、垫片 O-ring	三元乙丙橡胶、聚四氟乙烯、氟橡胶、硅橡胶 EPDM,PTFE,Vtion,Silicone

连接
Connection

壳体连接 Connection of shell	法兰 (吊环螺栓) Flange(Eyebot)
进出口 N1、N2 In-outlet	快装 Tri-clamp
压力表 N3 (选配) N3 Pressure gauge(option)	1.5" 快装 Tri-clamp
排气阀 N4 (选配) N4 Vent valve(option)	1/2" 快装 (12 芯以下) 1/2" Tri-clamp(less than 12pcs) 1.5" 快装 (15 芯以上) 1.5" Tri-clamp(more than 15pcs)
排液阀 N5 (选配) N5 Drain valve (option)	1/2" 快装 (3 芯) 1/2" Tri-clamp(3R) 3/4" 快装 (5 芯到 12 芯) 3/4" Tri-clamp(5pcs to 12pcs) 1" 快装 (15 芯以上) 1" Tri-clamp(more than 15pcs)
滤芯接头形式 Cartridges connection	222 型、226 型、DOE 222type, 226type,DOE

尺寸参数表
Dimension parameters

	3 芯 (4 芯) 3R(4R)			5 芯 (6 芯) 5R(6R)		
	20"	30"	40"	20"	30"	40"
A: 总高 (不含压力表) Total height	1123	1373	1623	1145	1395	1645
B: 进口中心距 The distance from inlet to center	142			165		
C: 直径 Shell diameter	Φ204			Φ250		
D1: 进口 N1 离地高度 The height from inlet to ground	540			660		
D2: 出口 N2 离地高度 The height from outlet to ground	300			300		
N1、N2: 进出口尺寸 In-outlet N1、N2 size	1.5"/2"			1.5"/2"/2.5"		
	7 芯 (7R)			8 芯 (8R)		
	20"	30"	40"	20"	30"	40"
	1145	1395	1645	1170	1420	1670
	176.5			190		
	Φ273			Φ300		
	660			660		
	300			300		
	1.5"/2"/2.5"			1.5"/2"/2.5"/3"		
	9 芯 (10 芯) 9R(10R)			12 芯 (11 芯) 12R(11R)		
	20"	30"	40"	20"	30"	40"
	1170	1420	1670	1170	1420	1670
	202.5			215		
	Φ325			Φ350		
	660			660		
	300			300		
	1.5"/2"/2.5"/3"			1.5"/2"/2.5"/3"		
	15 芯 (18 芯) 15R(18R)	21 芯 (21R)	24 芯 (27/30 芯) 24R(27/30R)	36 芯 (36R)	42 芯 (42R)	48 芯 (54 芯) 48R(54R)
	40"	40"	40"	40"	40"	40"
	1947	1959	2026	2036	2044	2067
	240	265	290	315	340	365
	Φ400	Φ450	Φ500	Φ550	Φ600	Φ650
	682	694	714	729	734	744
	300			300		
	3"/3.5"/4"			3"/3.5"/4"		

上表数据为标准 222、226 型工业级精密过滤器，仅供参考，可根据客户要求定制：未注长度单位为 mm。
The above-mentioned data is the standard, it can customize according to customer's requirements.

BYGSF 选型表
Selection Table

滤芯数量 Qty. of cartridge		滤芯型号 Model of cartridge	滤芯接头 Cartridges connection	壳体材料 Shell material	进出口连接 In-outlet connection	密封圈 O-ring
12R		20	S	4	K	E
3R=3 芯 Pcs	21R=21 芯 Pcs	20=20" 滤芯 Cartridge	S=226 型 Type	4=304	K= 快装 Tri-clamp	E= 三元乙丙橡胶 EPDM
5R=5 芯 Pcs	24R=24 芯 Pcs	30=30" 滤芯 Cartridge	T=222 型 Type	6=316L	E= 法兰 Flange	P= 聚四氟乙烯 PTFE
7R=7 芯 Pcs	36R=36 芯 Pcs	40=40" 滤芯 Cartridge	D=DOE 型 Type		L= 螺纹 Screw thread	V= 氟橡胶 Viton
8R=8 芯 Pcs	42R=42 芯 Pcs					S= 硅橡胶 Silicone
9R=9 芯 Pcs	48R=48 芯 Pcs					
12R=12 芯 Pcs	56R=56 芯 Pcs					
15R=15 芯 Pcs						

BYGRP

工业过滤器
Industrial Cartridge Filter




水处理过滤器
Water Treatment Precision Filter

- 平口过滤器具有一个卡箍式的盖子。滤芯接口设计酒杯可适用平口和 222 滤芯。这种平口过滤器结构成本最少并且适用于低压和初过滤。
- Industrial Cartridge filter has a clamp closures . All Cartridge filter are designed with Universal cartridge cups, allowing cartridges 222 or flat end.This type filter construction is suitable for low pressure situation and prefilter with lowest cost.

典型的应用
Typical application

- 平口过滤器可适用于化工厂过滤,水处理系统 ,RO 系统的保护作用。
- Chemical Industrial s' filtration Water treatment system Protection for RO system.




技术特性表
Technical specification

名称 Name	容器内 Inner surface
最大工作压力 (MPa) Max Operate Pressure	0.7
最大工作温度 (°C) Max Operate Temp	110
焊缝系数 Pressure Tolerance on Weld	0.85
腐蚀裕度 (mm) Corrosion By Acid	0

主要技术参数
Main parameters

序号 Item	No. of Cartridges	A				B				C	D	E	F
		10"	20"	30"	40"	10"	20"	30"	40"				
ZTRP-03R	3-5R	577	777	1027	1277	320	570	820	1070	205	170	125	80
ZTRP-07R	7R	537	787	1037	1287	320	570	820	1070	250	170	125	80
ZTRP-9R	9-12R	547	797	1047	1297	320	570	820	1070	300	170	125	80
ZTRP-15R	15R	599	849	1099	1349	320	570	820	1070	350	170	125	80
ZTRP-18R	18R	617	867	1117	1367	320	570	820	1070	400	170	125	80



序 号 Item	ZT=ZTRP	
2= 连接形式 Cartridge adaptor	T=222	
	S=226	
	D=DOE	
3= 滤芯数量 Qty of Cartridg	R:3-12	
4= 滤芯高度 Cartridge length	20=20inch	
	30=30inch	
	40=40inch	
5= 接口连接标准 Connection standard	BF=BSPF	BM=BSPM
	D=DIN	A=ANSI
	TC=Clamp	J=JIS
	NM=NPTM	NF=NPTF
6= 进出口尺寸 Inlet/outlet dimension	PM=PTM	PF=PTF
	10=1"	15=1.5"
	20=2"	25=2.5"
7= 材料 Construction material	30=3"	40=4"
	4=SS304	6=SS316L
8= 密封材料 Gasket material	E=EPDM	P=PTFE
	V=Viton	S=Sililone
9= 表面处理 Surface finish	A 电解抛光 Electrical polish	B= 镜面抛光 Mirror Polish
	C 喷砂 Sand blasted	D= 哑光抛光 Matt ppolish
	E 酸洗 Acid washing	F=2B
		2B

应用领域 Applications


- 我厂产品广泛应用在制药、食品、乳品、流体设备、啤酒、化工、石油、电力等行业。
- Our products are widely used in pharmaceutical, food, dairy, fluid equipment, beer, chemical, petroleum, electric power and other industries.



销售网络 Quality Control

随着在管件行业的不断成长我们一直在寻找机会，以充分发展博瑜在产品和流程方面的优势充分利用全球分销网络以及开发综合解决方案的能力，我们的核心战略是继续开发博瑜独特的优势市场并为该市场的客户提供与众不同的高价值服务。

As we continue to grow in the pipe fittings industry, we are always looking for opportunities to fully develop our advantages in products and processes. We leverage our global distribution network and the ability to develop integrated solutions. Our core strategy is to continue to develop our unique Advantage market and provide differentiated high value services to customers in this market.



About us

关于我们

18⁺
年
从事阀门事业

50⁺
个
产品应用行业

200⁺
种
产品种类多元化

10⁺
种
产品执行标准

温州优立机械有限公司创建于2002年，从事阀门事业近20年。总部位于温州市龙湾区高新技术园区度山工业区。是一家集研发、铸造、生产、销售及服务为一体的全能型阀门制造企业。

企业拥有现代化标准生产车间，雄厚的经济实力，完善的生产设备，专业的技术团队，是富睿稳步发展的基石。富睿产品以品质至上赢得口碑，靠品类丰富占有市场。所生产产品都经过严格的检验与检测，做到有瑕疵产品坚决不进入下一流程，不合格产品坚决不出车间，不会让不良品流入客户手中。为稳步拓展市场，企业现有研发生产的产品种类200多个型号，1000多种规格。

专业制造生产不锈钢阀门系列：电动阀门、气动阀门、L型三通球阀，T型三通球阀，单L型四通球阀、双L四通球阀、T型四通球阀、T型五通球阀、L型五通球阀、非标五通球阀、过滤器，闸阀，止回阀，截止阀，S型截止阀，B型截止阀，旋启式止回阀，立式止回阀，Y型过滤器，对夹式止回阀，快速接头，KJA槽车快速接头，KJB槽车快速接头，不锈钢快速接头，铝合金快速接头，铜制快速接头，液压快速接头，一片式球阀，二片式球阀，三片式球阀，对焊球阀，快装球阀，承插焊球阀，内螺纹球阀，法兰球阀，卫生级球阀，卫生级隔膜阀，卫生级法兰球阀，Z15闸阀，H14止回阀，H12止回阀，JB11截止阀，JS11截止阀，GY11过滤器，H71止回阀，Z41闸阀，H44止回阀，H42止回阀，J41截止阀，GY41过滤器，Q11球阀，Q15球阀，Q14球阀，Q21球阀，Q41球阀，Q61球阀，Q71球阀，Q81球阀，G81隔膜阀，D81蝶阀，管件、弯头、三通、堵头、管帽、活接、外丝、内丝、皮干接、等其它非标产品订做。

公称通径：DN15mm-DN300mm (1/4 " -12 ")。
公称压力：PN0.6Mpa-6.4Mpa (Class150LB-600LB)。
连接方式：丝扣，快装，法兰，焊接等方式。
驱动方式：进口（国产）气动，电动，蜗轮，液动等方式。

产品广泛应用于水务，石油，化工，造纸，电站，船舶，轻纺，建筑，水利，制药，环保等诸多行业。在标准化规范化发展前提下，企业先后获得国家压力管道TS证书、国际质量体系ISO9001-2015证书、欧盟CE证书、多枚国家商标证书、多项专利等证书和荣誉。产品也远销海外，遍及美国，日本，欧洲，东南亚，南非等国家和地区。企业以创新带发展、质量求生存、管理促效益、诚信引客户的经营理念，“诚心服务、注重品牌”取信于新老客户，服务于新老客户。欢迎各界新老朋友来电来函咨询。真诚欢迎各界用户前来参观、考察、洽谈业务！



YouLi Machinery Co., Ltd. was founded in 2002 and has been engaged in valve business for nearly 20 years. The headquarter is located in Dushan Industrial Zone, High-tech Park, Longwan District, Wenzhou City. It is an all-round valve manufacturing enterprise integrating R&D, casting, production, sales and service.

The company has modern standard production workshops, strong economic strength, perfect production equipment, and professional technical team, which are the cornerstones of Fu Rui's steady development. Furui's products have won a reputation for quality first, and they occupy the market with rich categories. The products produced have undergone strict inspection and testing, so that defective products will never enter the next process, unqualified products will never leave the workshop, and defective products will not flow into the hands of customers. In order to steadily expand the market, the company currently develops and produces more than 200 types of products and more than 1,000 specifications.

Professional manufacturing and production of stainless steel valve series: electric valves, pneumatic valves, L-type three-way ball valves, T-type three-way ball valves, single L-type four-way ball valves, double-L four-way ball valves, T-type four-way ball valves, T-type five-way ball valves, L-type five-way ball valve, non-standard five-way ball valve, filter, gate valve, check valve, stop valve, S-type stop valve, B-type stop valve, swing check valve, vertical check valve, Y-type filter, Wafer check valve, quick coupling, KJA tank truck quick coupling, KJB tank truck quick coupling, stainless steel quick coupling, aluminum alloy quick coupling, copper quick coupling, hydraulic quick coupling, one-piece ball valve, two-piece ball valve, Three-piece ball valve, butt welding ball valve, quick-fit ball valve, socket welding ball valve, internal thread ball valve, flange ball min, sanitary ball valve, sanitary diaphragm valve, sanitary flange ball valve, Z15 gate valve, H14 check valve, H12 check valve, JB11 globe valve, JS11 globe valve, GY11 filter, H71 check valve, Z41 gate valve, H44 check valve, H42 check valve, J41 globe valve, GY41 filter, Q11 ball valve, Q15 ball valve, Q14 ball valve, Q21 ball valve, Q41 ball valve, Q61 ball valve, Q71 ball valve, Q81 ball valve, G81 diaphragm valve, D81 butterfly valve, pipe fittings, elbows, three-way, plugs, pipe caps, unions, outer wires, inner wires, skin dry Other non-standard products are customized.

Nominal diameter: DN15mm-DN300mm (1/4"-12").
Nominal pressure: PN0.6Mpa-6.4Mpa (Class150LB-600LB).
Connection methods: threaded, quick installation, flange, welding, etc.
Drive mode: imported (domestic) pneumatic, electric, worm gear, hydraulic, etc.

Products are widely used in water, petroleum, chemical, paper, power station, shipbuilding, textile, construction, water conservancy, pharmaceutical, environmental protection and many other industries. Under the premise of standardized development, the company has successively obtained the national pressure pipeline TS certificate, the international quality system ISO9001-2015 certificate, the EU CE certificate, multiple national trademark certificates, multiple patents and other certificates and honors. Products are also exported to overseas, all over the United States, Japan, Europe, Southeast Asia, South Africa and other countries and regions. With the business philosophy of innovation to drive development, quality to survive, management to promote efficiency, and integrity to attract customers, the company "sincere service and focus on brand" wins the trust of new and old customers and serves new and old customers. Welcome new and old friends from all walks of life to call or write for consultation. Sincerely welcome users from all walks of life to visit, inspect and negotiate business!